



HIGH-EFFICIENT COMBINED HEAT AND POWER FACILITY UTILIZING RENEWABLE SOURCES (OHB II - LINE K1)



# Safety first

# **Site safety**



# **Covid measures**



Masks



Wash hands

Distancing



# **General information on public procurement**

### **Procurement regime**

Over-the-limit utilities contract for construction works awarded in a negotiated procedure with prior publication as per provisions of Section 60 of the PPA.

### Main stages

- > Qualification *completed*
- Call for indicative tenders ongoing
- Negotiation of indicatives tenders
- Call for final tenders
- Evaluation of final tenders

### Important note:

All the information provided during site visit are exclusively of informative nature and therefore are not binding to the contracting authority.



# **Evaluation criteria**

|       | Evaluation criteria                                   | Weight      |
|-------|---|-------------|
| K.1   | Overall financial advantageousness                    | <b>70</b> % |
| К.2   | Quality of performance                                | 25 %        |
| K.2.1 | Proposed technology and solution concept              | 75 %        |
| K.2.2 | Technical guarantees                                  | 15 %        |
| K.2.3 | Environmental parameters                              | 10 %        |
| К.3   | Layout of the construction and technological solution | 5 %         |

### The most important evaluation parameters

- Net present value of the project in 7 years
  - Significant impact of balance price/efficiency
  - Potential bonus for shorter construction period
- > Well specified, comprehensive and robust solution
- > Tender with detail descriptions (design, execution, management)

| 1. Základní provozní předpoklad / General operational assumption        |                      |  |  |
|---|----------------------|--|--|
| 1.1 Zpracovaný odpad / Proccessed waste                                 | tun/rok (tons/annum) |  |  |
| 1.2 Výhřevnost odpadu / Waste LHV MJ/kg                                 |                      |  |  |
| 1.3 Roční disponibilita / Annual availability                           | h                    |  |  |
| 2. Roční bilance produkce energií / Annual balance of energy production |                      |  |  |
| 2.1 Dodané teplo / heat delivered                                       | GJ                   |  |  |
| 2.2 Čistá výroba el.energie / net electricity production                | MWh                  |  |  |

| 3. Roční výnosy / Annual income          |  |
|--|--|
| 3.1 Prodej tepla / Heat sales            |  |
| 3.2 Prodej elektriny / electricity sales |  |
| 3.3 Celkem / In total                    |  |

| 4. Roční náklady provozu / Aannual operational expenditure      |  |  |  |
|---|--|--|--|
| 4.1 Regular maintenance   |  |  |  |
| 4.2 Wear parts  |  |  |  |
| 4.3 Spotřeba vody - kotel / w ater consumption - boiler         |  |  |  |
| 4.4 Spotřeba pitné vody / fresh w ater consumption              |  |  |  |
| 4.5 Spotřeba močoviny / urea consumption                        |  |  |  |
| 4.6 Spotřeba nehašeného vápna / quick lime consumption          |  |  |  |
| 4.7 Spotřeba hydroxidu vápenatého / hydrated lime               |  |  |  |
| consumption   |  |  |  |
| 4.8 Spotřeba aktivního uhlí / active carbon consumption         |  |  |  |
| 4.9 Spotřeba stlačeného přístrojového vzduchu / instrument      |  |  |  |
| air consumption   |  |  |  |
| 4.10 Spotřeba stlačeného procesního vzduchu / process air       |  |  |  |
| consumption   |  |  |  |
| 4.11 Odpad - škvára / IBA residue                               |  |  |  |
| 4. 12 Popel z kotle a zbytky ze systému čištění spalin / Boiler |  |  |  |
| ash and FGT residue   |  |  |  |
| 4.13 *Spotřeba ostatních chemikálií / other reagents            |  |  |  |
| consumption   |  |  |  |
| 4.14 Celkem / In Total  |  |  |  |





# **INVESTOR DESCRIPTION**



# **Investor description**

**SAKO Brno, a.s. as municipality owned company** operates independently and provides services for Brno city (open-ended contract) and to others:

Collection

>

>

Municipal waste

Recyclables

**Collection centers** 

Mixed municipal waste

- Waste collection
- Recycling
- Waste disposal by energy utilization



 Education program (schools & public)

# Main company area of the operation

### SAKO Brno, a.s.

Experienced operator of WtE since 1994



# SAKO BRNO, a.s. – Existing Waste-to-Energy plant

### **Existing line K2 and K3**

- Plant from 1980's, refurbished in 2010
- > 2x14 ton/h identical EfW lines
- 2 manual waste cranes
- Vertical 5-pass steam boilers, Steam parameters: 40 bar/400°C
- Extraction steam turbine, 20 MWe
- > Air-cooled condenser
- SNCR, bagfilter & semi-dry FGT system
- Production of electricity and district heating (DH), both steam and hot water



# **PROJECT DESCRIPTION**





# **PUBLIC CONTRACT**



# **Envisaged Project and Contractual structure**

### **Project procurement phase**

Project procurement phase under cooperation with experienced advisors:

- Ramboll Group A/S : technical advisor
- PricewaterhouseCoopers : financial advisor
- Legal team: MT Legal

### **Project structure**

- Design & Build project engaged under EPC contract
- Fixed lump-sum contract

### Anticipated financing structure

- Own equity in combination with corporate financing
- Subsidy from Modernization fund (in negotiation)





# **Site conditions**

### **Major highlights**

- Urban area (distance to residential area 150 meters)
- Limited area in place of construction
- > Parallel construction projects
- Full operation of existing facility
- Strict noise and dust requirements

### Available areas for site facilities

- P1 ca. 62 m2
- P2 ca. 125 m2
- P3 ca. 1400 m2
- P4 ca. 740 m2
- P5 ca. 2100 m2;
- ➢ P6 − ca. 4500 m2;
- P7 ca. 10000 m2;









# Most demanding battery limits

### **Investor's priorities**

1. Safety first

2. Continuous operation of existing WtE plant

3. Upfront detail planning of most demanding tasks





# **Project scope**

### New K1 line

- > New boiler hall
- > 180° U turn flue gas treatment
- Extension of bunker
- Automatic cranes
- Backpressure turbine's machine hall
- Interconnection of new DH lines- DN600
- Control room relocation
- Existing auxiliaries relocation
- Existing stack utilization
- Former K1 existing space utilization





# **Emphasis on efficiency** $\rightarrow$ **Highly efficient CHP**

### **Operational energy efficiency**

- Maximal utilization of residual waste energy potential
- Flue gas and cooling system waste heat utilization
- Absorbtion heat pump
- Emphasis on flexibility of heat and electricity supply





# Key design basis requirements





Semi-Dry Flue Gas Treatment System and downstream LT ECO and flue gas condensation.

| Air emission at stack                      |  | BATAELs                      |                                   |                                   |  |
|--|--|------------------------------|-----------------------------------|-----------------------------------|--|
| Substance                                  | Unit<br>ref=(11% 0 <sub>2</sub> , dry)         | NEW plants                   | EXISTING plants                   | Sampling period                   |  |
| Dust                                       | mg/Nm <sup>3</sup>                             | <2-5                         |                                   | Daily                             |  |
| тиос                                       | mg/Nm <sup>3</sup>                             | < <b>3-10</b> <sup>(6)</sup> |                                   | Daily                             |  |
| со   | mg/Nm <sup>3</sup>                             | 10-50                        |                                   | Daily                             |  |
| нсі  | mg/Nm <sup>3</sup>                             | <2-6                         | <2-8                              | Daily                             |  |
| HF   | mg/Nm <sup>3</sup>                             | <1 (6)                       |                                   | Daily 1                           |  |
| SO <sub>2</sub>                            | mg/Nm <sup>3</sup>                             | 5-30                         | 5-40                              | Daily                             |  |
| NO <sub>x</sub> (SCR, SNCR)                | ma (Nm3  | 50-120                       | 50-150                            | Daily                             |  |
| SNCR, if SCR not possible                  | ing/initi-                                     |                              | up to 180                         | Daily                             |  |
| NH₃ (SCR or SNCR)<br>(Exist. SNCR not wet) | mg/Nm <sup>3</sup>                             | 2-10                         | 2-10 (15)                         | Daily                             |  |
|  |  | <5-20                        |                                   | Daily 2, 3                        |  |
| Hg   | µg/Nm³   | 1-10                         |                                   | Long term sampling $^{2}$         |  |
|  |  | <5                           | -20                               | Periodic, short term <sup>2</sup> |  |
| PCDD/F 5                                   | ng <sub>I-TEQ</sub> /Nm <sup>3</sup>           | <0.01-0.06                   | <0.01-0.08                        |                                   |  |
| PCDD/F + PCB-DL 5                          | ng <sub>I &amp; wно-теq</sub> /Nm <sup>3</sup> | <0.01-0.08                   | <0.01-0.1                         | Long term sampling <sup>5</sup>   |  |
| PCDD/F <sup>5</sup>                        | ng <sub>I-TEQ</sub> /Nm <sup>3</sup>           | <0.01-0.04                   | <0.01-0.06                        |                                   |  |
| PCDD/F + PCB-DL 5                          | ng I & WHO-TEQ/Nm <sup>3</sup>                 | <0.01-0.06                   | <0.01-0.08                        | Periodic, short term              |  |
| Cd+TI                                      | mg/Nm <sup>3</sup>                             | 0.005                        | 0.005 - 0.02 Periodic, short term |                                   |  |
| Sb+As+Pb+Cr+Co+Cu+Mn+Ni+V                  | mg/Nm <sup>3</sup>                             | 0.01-0.3 Periodic, short t   |                                   | Periodic, short term              |  |

<sup>(1)</sup>: HF continuous measurement may be replaced by periodic measurements if HCl emission are proven to be sufficiently stable (BAT4).

<sup>(2)</sup>: Hg continuous measurement may be replaced by long-term sampling or periodic measurements if incinerated waste Hg content proven low and stable (e.g. mono-streams of waste of a controlled composition) (BAT4).

(3): Hg ½\_hr average indicative value (not BATAELs) for new plants 15-35 µg/Nm<sup>3</sup>, for existing 15-40 µg/Nm<sup>3</sup> (BAT31).

<sup>(4)</sup>: Either the BATAELs for PCDD/F or the BATAELs for PCDD/F + PCBs-DL apply. PCB-DL monitoring does not apply if PCB-DL are proven to be less than 0.01 ng  $_{WHO-TEQ}/Nm^3$  (BAT30).

<sup>(5)</sup>: The long term sampling BATAELs do not apply if the emission levels are proven to be sufficiently stable (BAT30).



# **Energy system - Highlights**

### **Combined Heat & Power**

- Moderate steam parameters: 400°C / 40 bar
- Efficient and flexible CHP production
- New back-pressure turbine optimized for DH production
- Increased electricity production of existing turbine by replacing in-efficient DH production with new efficient DH production
- Two-step flue gas condensation: direct and heat pump\* driven which cools the flue gas to 41 °C
- Energy recovery from component cooling to DH





# **Civil part** $\rightarrow$ **Existing buildings**

| BO 101/1 – Waste       | Medium impact   |
|------------------------|---|
| Bunker                 | Installation of new cranes and control room and all necessary accessories (e.g. fire safety, etc.).   |
| BO 102/1 – Boiler hall | Demolition of the dividing wall above the level of the existing boiler hoppers.<br>Disassembly of crane cabins and fire protection equipment.<br>Minor impact |
|                        | Linking and delivery of the slag conveyor to the slag bunker.   |
|                        | Linking to service platforms and lift in required levels.   |
| BO 103/1 – Slag        | Linking/installation of new fire pumps.<br><b>Small impact</b>  |
| treatment hall         | Linking a joint drainage from the new line to the existing slag bunker.   |
| BO 106 – Trafoes and   | Wastewater linked to a slag waste-water sump.<br><b>Medium impact</b>   |
| electrical building    | Demolition of a part of the building (stair tower) for connection of the service route and removal of the slag conveyor.                                      |
| BO 401 – Sorting and   | Small impact  |
| turbine hall           | Installation of an independent steel platform above the existing roof structure.  |
| BO 412 – District      | Medium impact   |
| heating station        | Connection of hot water pipes for heat dissipation from the new K1 technology.  |
| BO 108 – Maintenance   | High impact   |
| and locker room        | Will need to be demoliched  |
| building               |   |
| Building (chemical     | High impact   |
| water treatment)       | Will need to be demolished.   |



### **New buildings**

BO 501 – Extension of the waste bunker

BO 502 – K1

flue gas

**Boiler hall and** 

New bunker connected to an existing bunker without new feed-in gate. All waste will be received through existing dumps.

The new bunker will be linked to the existing BO 101 via new crane tracks.

The new boiler and flue gas treatment hall will be connected to an extended bunker. All technology related to the new K1 incinerator line will be installed in this new building.



# **Civil part and Architecture**

### **Major highlights**

- Combination of polycarbonate and sandwich paroc panels
- Emphasis on quality and proven materials with long-term lifespan
- Integrated RGWB illumination with advance control system
- Accessible green walking roof for future visits
- United facade of new and existing building











# **PROJECT TIMELINE**



# **Project timeline and day-to-day status**

| Activity  | Start   | Finish  | Status    |
|---|---------|---------|-----------|
| Conceptual design                                       | 04/2019 | 09/2019 | Finalized |
| Architectural study                                     | 09/2019 | 12/2019 | Finalized |
| Feasibility study                                       | 09/2019 | 11/2019 | Finalized |
| Waste availability study                                | 09/2019 | 11/2019 | Finalized |
| Future DH delivery study                                | 09/2019 | 12/2019 | Finalized |
| Project definition                                      | 12/2019 | 05/2020 | Finalized |
| EIA   | 08/2019 | 01/2021 | Finalized |
| Zoning permission                                       | 09/2019 | 08/2021 | Finalized |
| Integrated pollution prevention control permission      | 11/2020 | 11/2021 | Finalized |
| Contracts for main utilities (waste; heat; electricity) | 01/2020 | 12/2021 | Finalized |
| Public procurement preparation                          | 10/2019 | 09/2021 | Finalized |
| Finance raising and Insurance process                   | 01/2020 | 08/2022 | Ongoing   |
| Public procurement (Owner's engineer)                   | 10/2021 | 04/2022 | Ongoing   |
| Public procurement (Contractor)                         | 07/2021 | 08/2022 | Ongoing   |
| City council approval procedure                         | 08/2022 | 09/2022 |           |
| Project construction                                    | 10/2022 | 10/2025 |           |

# SAKU

SAKO Brno, a.s. Jedovnická 2, 628 00 Brno, Česká republika tel.: +420 548 138 217 mobil: +420 603 140 618 e-mail: reditelstvi@sako.cz, www.sako.cz

This document is confidential and cannot be used in any way without the written consent of the company SAKO Brno, a.s.